



Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)
 Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara,
 Pin Code : 391775. Gujarat, India.
 Telephone : 02667-264007, +91 86660 09021
 Email : erto@erto.in / sr.patel@erto.in
 Web : http://www.erto.in



ERTO

Quality Assurance Laboratory



Certificate no. TC-6229

TEST REPORT

Report No	: ERTO/TRP/1819/0820
ULR No.	: TC622919000000186F
Date of issue	: 16/03/2019
Total number of pages	: 26
Customer's name	: RECONS POWER EQUIPMENTS PVT. LTD.
Address	: Plot No. 38, Sector-25, Faridabad -121004, Haryana (INDIA).
Customer's reference & date	: RP/18-19/ERTO/009, dated 16/02/2019
Test specification	
-Standard	: As per IS 1180 (Part 1):2014 with amendment no. 1 & 2
-Test procedure	: As per IS 1180 (Part 1):2014 with amendment no. 1 & 2
-Non-standard test method	: N/A
ERTO sample ID no.	: ERTO-0908
Test performed at	: ERTO lab
Name of test sample	: 2500 kVA Distribution Transformer
Make	: RECONS POWER EQUIPMENTS PVT. LTD.
Rating	: 2500 kVA
Technical specification of test sample	: As per page 2.
Test performed	: As per page 5.
Any other details specified by customer:	: ---
Date of receipt of test sample	: 25/02/2019
Condition on Receipt	: Good
Date(s) of performance of test(s)	: 28/02/2019 to 09/03/2019
Tests witnessed by	: Mr. Mahendra Yadav (Manager-Operations, M/s. Recons Power Equipments Pvt. Ltd.)
List of Enclosures	
-Test sample photo	: As per page 3.
-Rating plate photo	: As per page 4.
-Drawings (As submitted by customer)	: 1) RC/18-19/2500/01 REVISION 00 2) RC/18-19/2500/02 Sh 1/1
Remarks	: 1) The sample conforms to the requirements of above mentioned standard for the test nos. 2, 5, 6 & 8 to 14. 2) The observations of the test nos. 1, 3, 4, 7 & 15 are as per page 6 to 9 & 26.
Prepared By	<i>Epai ney</i> Prepared By
Checked By	<i>Yash J. Shah</i> Checked By (Yash J. Shah)
Approved By	<i>S.R. Patel</i> Approved By (S.R. Patel) (Technical Director)
Notes:	<ol style="list-style-type: none"> This report relates only to the particular sample tested. Only the tests asked by the customer have been carried out. This report cannot be reproduced in part under any circumstances. Publication of this report requires prior permission in writing from Technical Director, ERTO. In case of any dispute, ERTO will be the exclusive jurisdiction & shall be construed as where the cause has arisen. <p>Caution: ERTO is not responsible for the authenticity of photocopied or reproduced test reports. ERTO provides support to customers for verification of the authenticity of test reports issued by ERTO.</p>





Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)
Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.

Pin Code : 391775. Gujarat, India.
Telephone : 02667-264007, +91 88660 09021
Email : erto@erto.in / sr.patel@erto.in
Web : http://www.erto.in



ERTO

Quality Assurance Laboratory



Certificate no, TC-6229

Report No.: ERTO/TRP/1819/0820

ULR No.: TC622919000000186F


Date: 16/03/2019

Technical Specification of Test Sample declared by customer

1. Test sample : 2500 kVA Distribution Transformer (Non sealed type)
2. Name of manufacture : RECONS POWER EQUIPMENTS PVT. LTD.
3. Serial No. : 5432/02/19
4. Rating : 2500 kVA
5. Energy efficiency level : 3
6. Rated voltage at no load H.V/L.V : 33000/433 Volt
7. Rated current at H.V/L.V : 43.73/3333.43 Amp.
8. Number of phases : 3-Phase
9. Connection H.V./L.V : Delta/Star
10. Frequency : 50 Hz
11. Type of cooling : ONAN
12. Temperature rise of oil/winding : 40/45 °C
13. Percentage Impedance (HV to LV) : 6.25 %
14. Vector group : Dyn11
15. Winding material : Copper
16. Year of manufacture : 2019
17. Max. total loss at 50% load at 75°C : 6342.5 W
18. Max. total loss at 100% load at 75°C : 18812.5 W
19. Basic insulation level of H.V. : 70 kVrms/170 kVp
20. Basic insulation level of L.V. : 03 kVrms
21. Tapping details :

Tap position	HV Taps (volts)	LV (volts)
1	36300	433
2	35475	433
3	34650	433
4	33825	433
5	33000	433
6	32175	433
7	31350	433

ERTO Sample ID No. : ERTO-0908



Prepared By
Prepared By



Checked By
Checked By



Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)
 Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.
 Pin Code : 391775. Gujarat, India.
 Telephone : 02667-264007, +91 88660 09021
 Email : erto@erto.in / sr.patel@erto.in
 Web : http://www.erto.in



ERTO

Quality Assurance Laboratory



Certificate no. TC-6229

Report No.: ERTO/TRP/1819/0820

ULR No.: TC622919000000186F

Date: 16/03/2019

Test Sample photo



Prepared
Prepared By

Checked
Checked By





Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)

Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.

Pin Code : 391775. Gujarat, India.

Telephone : 02667-264007, +91 88660 09021

Email : erto@erto.in / sr.patel@erto.in

Web : http://www.erto.in



ERTO

Quality Assurance Laboratory



Certificate no. TC-6229

Report No.: ERTO/TRP/1819/0820

ULR No.: TC622919000000186F

Date: 16/03/2019

Rating Plate Photo

DISTRIBUTION TRANSFORMER
RECONS POWER EQUIPMENTS PVT. LTD.
 FARIDABAD - 211004
 PH : (0129) 4082114 - 6

3 PHASE TRANSFORMER

STANDARD	IS 1160 (PART 1)	ENERGY EFFICIENCY LEVEL	3
KVA	2500	MAX. TOTAL LOSSES AT 20% RATED LOAD W	3342.5
VOLTS AT NO LOAD	HV	33000	MAX. TOTAL LOSSES AT 100% RATED LOAD W
	LV	433	
BIL	HV	170/70	TYPE OF COOLING
	LV		ONAN
AMPERES	HV	43.73	TEMP. RISE
	LV	3333.43	
FREQUENCY Hz	50		Wdg °C
VECTOR GROUP	Dyn 11	MASS OF OIL	KG
IMPEDANCE VOLT %	6.25	TOTAL MASS	KG
TAPPINGS	OFF CKT.	VOLUME OF OIL	LTR
FOR HV VARIATION		MONTH & YEAR OF MFG.	FEB. 2019
IN 2.5 STEPS FROM +10 % TO -5 %		SERIAL NO.	843202/19
CUSTOMER			
ORDER NUMBER			

MADE IN INDIA

SWITCH POSITION	CONNECTIONS	NO LOAD VOLTAGE	
		HV	LV
1	5-5	33300	433
2	6-4	35475	433
3	4-7	34550	433
4	7-3	33825	433
5	3-8	33000	433
6	8-2	32175	433
7	2-9	31350	433

Prepared By
Prepared By



Checked By
Checked By



Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)

Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.

Pin Code : 391775. Gujarat, India.

Telephone : 02667-264007, +91 88660 09021

Email : erto@erto.in / sr.patel@erto.in

Web : http://www.erto.in



ERTO

Quality Assurance Laboratory



Certificate no. TC-6229

Report No.: ERTO/TRP/1819/0820

ULR No.: TC622919000000186F

Date: 16/03/2019

Tests performed :

Sr. No.	Test details	Test specifications
1.	Measurement of winding resistance	As per cl.no.21.2. (a) of IS 1180 (Part 1) : 2014
2.	Measurement of voltage ratio and check of phase displacement.	As per cl.no.21.2.(b) of IS 1180 (Part 1) : 2014
3.	Measurement of short-circuit impedance and load loss at 50 percent and 100 percent load.	As per cl.no.21.2. (c) of IS 1180 (Part 1) : 2014
4.	Measurement of no-load loss and current	As per cl.no.21.2. (d) of IS 1180 (Part 1) : 2014
5.	Total losses at 50 percent load	As per cl.no.7.8 of IS 1180 (Part 1) : 2014
6.	Total losses at 100 percent load	As per cl.no.7.8 of IS 1180 (Part 1) : 2014
7.	Measurement of insulation resistance	As per cl.no.21.2. (e) of IS 1180 (Part 1) : 2014
8.	Induced over-voltage withstand test.	As per cl.no.21.2 (f) of IS 1180 (Part 1) : 2014
9.	Separate-source voltage withstand test.	As per cl.no.21.2 (g) of IS 1180 (Part 1) : 2014
10.	Pressure test (Routine)	As per cl.no.21.2 (h) of IS 1180 (Part 1) : 2014
11.	Oil leakage test	As per cl.no.21.2 (j) of IS 1180 (Part 1) : 2014
12.	Lightning impulse test with chopping	As per cl.no.21.3(a) of IS 1180 (Part 1) : 2014 & test procedure followed as per cl. no. 14 of IS 2026 (Part 3): 2009
13.	Temperature-rise test	As per cl.no.21.3 (b) of IS 1180 (Part 1) : 2014
14.	Pressure test (type)	As per cl.no.21.3 (d) of IS 1180 (Part 1) : 2014
15.	Determination of sound levels	As per cl.no.21.4(a) of IS 1180 (Part 1) : 2014

Prepared By

Checked By





Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)

Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.

Pin Code : 391775. Gujarat, India.

Telephone : 02667-264007, +91 88660 09021

Email : erto@erto.in / sr.patel@erto.in

Web : http://www.erto.in



ERTO

Quality Assurance Laboratory



Certificate no. TC-6229

Report No.: ERTO/TRP/1819/0820

ULR No.: TC622919000000186F

Date: 16/03/2019

Sr. No.	Particulars of test & cl.no.	Requirements as per specifications	Obtain value	Remarks
1.	Measurement of winding resistance : (As per cl.no.21.2.(a) of IS 1180 (Part 1) : 2014)			---
	Average oil temperature		27.5 °C	
	HV Winding			
	Tap position 1			
	1U – 1V:		1.8412 Ω	
	1V – 1W:		1.8456 Ω	
	1U – 1W:		1.8421 Ω	
	Average:	---	1.8430 Ω	
	Tap position 2			
	1U – 1V:		1.8008 Ω	
	1V – 1W:		1.8053 Ω	
	1U – 1W:		1.8000 Ω	
	Average:	---	1.8020 Ω	
	Tap position 3			
	1U – 1V:		1.7594 Ω	
	1V – 1W:		1.7638 Ω	
	1U – 1W:		1.7592 Ω	
	Average:	---	1.7608 Ω	
	Tap position 4			
	1U – 1V:		1.7169 Ω	
	1V – 1W:		1.7198 Ω	
	1U – 1W:		1.7137 Ω	
	Average:	---	1.7168 Ω	
	Tap position 5			
	1U – 1V:		1.6722 Ω	
	1V – 1W:		1.6760 Ω	
	1U – 1W:		1.6695 Ω	
	Average:	---	1.6726 Ω	

Pranav
Prepared By



[Signature]
Checked By



Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)

Plot No. 747, Manjusr Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.

Pin Code : 391775, Gujarat, India.

Telephone : 02667-264007, +91 88660 09021

Email : erto@erto.in / sr.patel@erto.in

Web : http://www.erto.in



ERTO

Quality Assurance Laboratory



Certificate no. TC-6229

Report No.: ERTO/TRP/1819/0820

ULR No.: TC622919000000186F

Date: 16/03/2019

Sr. No.	Particulars of test & cl.no.	Requirements as per specifications	Obtain value	Remarks
	<p>Tap position 6</p> <p>1U – 1V: 1.6300 Ω</p> <p>1V – 1W: 1.6341 Ω</p> <p>1U – 1W: 1.6274 Ω</p> <p>Average: --- 1.6305 Ω</p> <p>Tap position 7</p> <p>1U – 1V: 1.5897 Ω</p> <p>1V – 1W: 1.5930 Ω</p> <p>1U – 1W: 1.5864 Ω</p> <p>Average: --- 1.5897 Ω</p> <p>LV Winding</p> <p>2u– 2v: 342.9 μΩ</p> <p>2v– 2w: 339.0 μΩ</p> <p>2u– 2w: 341.2 μΩ</p> <p>Average --- 341.0 μΩ</p>			---
2.	<p>Measurement of voltage ratio and check of phase displacement : (As per cl.no.21.2.(b) of IS 1180 (Part 1) : 2014)</p> <p>HV winding and LV winding:</p> <p>Tap position 1</p> <p>1U1V/2u2n: 145.20 (IS Tol.) 145.29</p> <p>1V1W/2v2n: 145.20 (IS Tol.) 145.35</p> <p>1W1U/2w2n: 145.20 (IS Tol.) 145.32</p> <p>Tap position 2</p> <p>1U1V/2u2n: 141.90 (IS Tol.) 142.02</p> <p>1V1W/2v2n: 141.90 (IS Tol.) 142.02</p> <p>1W1U/2w2n: 141.90 (IS Tol.) 142.01</p> <p>Tap position 3</p> <p>1U1V/2u2n: 138.60 (IS Tol.) 138.71</p> <p>1V1W/2v2n: 138.60 (IS Tol.) 138.70</p> <p>1W1U/2w2n: 138.60 (IS Tol.) 138.71</p>			Conforms
<p><i>Pranay</i> Prepared By</p>		<p><i>[Signature]</i> Checked By</p>		





Electrical Research & Testing organisation™

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)

Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.

Pin Code : 391775, Gujarat, India.

Telephone : 02667-264007, +91 88660 09021

Email : erto@erto.in / sr.patel@erto.in

Web : http://www.erto.in



ERTO

Quality Assurance Laboratory



Certificate no. TC-6229

Report No.: ERTO/TRP/1819/0820

ULR No.: TC62291900000186F

Date: 16/03/2019

Sr. No.	Particulars of test & cl.no.	Requirements as per specifications	Obtain value	Remarks
	<p>Tap position 4</p> <p>1U1V/2u2n: 135.30 (IS Tol.)</p> <p>1V1W/2v2n: 135.30 (IS Tol.)</p> <p>1W1U/2w2n: 135.30 (IS Tol.)</p> <p>Tap position 5</p> <p>1U1V/2u2n: 132.00 (IS Tol.)</p> <p>1V1W/2v2n: 132.00 (IS Tol.)</p> <p>1W1U/2w2n: 132.00 (IS Tol.)</p> <p>Tap position 6</p> <p>1U1V/2u2n: 128.70 (IS Tol.)</p> <p>1V1W/2v2n: 128.70 (IS Tol.)</p> <p>1W1U/2w2n: 128.70 (IS Tol.)</p> <p>Tap position 7</p> <p>1U1V/2u2n: 125.40 (IS Tol.)</p> <p>1V1W/2v2n: 125.40 (IS Tol.)</p> <p>1W1U/2w2n: 125.40 (IS Tol.)</p> <p>Vector Group: Dyn11</p>			
3.	<p>Measurement of short-circuit impedance and load loss at 50 percent and 100 percent load: (As per cl.no.21.2.(c) of IS 1180 (Part 1) : 2014) Supply connected on HV side and LV side short circuit. At 50% Load</p> <p>Tap position 5</p> <p>Average oil temperature</p> <p>Frequency</p> <p>Test current</p> <p>Impedance voltage</p> <p>Measured load loss</p> <p>Impedance voltage (Computed to 50% load)</p> <p>At 25.0 °C</p> <p>At 75°C</p> <p>Load loss (Computed to 50% load)</p> <p>At 25.0 °C</p> <p>At 75°C</p>		<p>25.0 °C</p> <p>49.856 Hz</p> <p>21.876 Amp.</p> <p>1019.82 V</p> <p>3427.20 W</p> <p>3.09 %</p> <p>3.10 %</p> <p>3425.31 W</p> <p>3790.80 W</p>	---
Prepared By		Checked By		





Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)

Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.

Pin Code : 391775, Gujarat, India.

Telephone : 02667-264007, +91 88660 09021

Email : erto@erto.in / sr.patel@erto.in

Web : http://www.erto.in



ERTO

Quality Assurance Laboratory





Certificate no. TC-6229

Report No.: ERTO/TRP/1819/0820

ULR No.: TC62291900000186F

Date: 16/03/2019

Sr. No.	Particulars of test & cl.no.	Requirements as per specifications	Obtain value	Remarks
	At 100% Load Average oil temperature Frequency Test current Impedance voltage Measured load loss Impedance voltage (Computed to 100% load) At 25.0°C At 75°C Load loss (Computed to 100% load) At 25.0°C At 75°C	6.25% (IS Tol.)	25.0 °C 49.868 Hz 43.732 Amp. 2039.64 Volts 13590.00 W 6.18 % 6.21 % 13594.94 W 15074.02 W	Conforms
4.	Measurement of no-load loss and current : (As per cl.no.21.2(d) of IS 1180 (Part 1) : 2014) Supply connected on LV winding and HV winding open-circuited. At 100% of rated voltage Mean voltage Frequency RMS voltage No-load current Measured no-load loss Corrected no-load loss	---	433.38 Volts 50.018 Hz 438.61 Volts 5.6476 Amps 2107.60 Watts 2082.10 Watts	---
5.	Total losses at 50 percent load (As per cl.no.7.8 of IS 1180 (Part 1) : 2014)	Max.6342.5 Watts	5872.9 Watts	Conforms
6.	Total losses at 100 percent load (As per cl.no.7.8 of IS 1180 (Part 1) : 2014)	Max.18812.5 Watts	17156.12 Watts	Conforms
7.	Measurement of insulation resistance : (As per cl.no.21.2(e) of IS 1180 (Part 1) : 2014) Average oil temperature Insulation resistance value HV winding to Earth at 5000 DC Volts for 60 seconds LV winding to Earth at 500 DC Volts for 60 seconds HV winding to LV winding at 5000 DC Volts for 60 seconds	---	27.1 °C 3.70 GΩ 3.01 GΩ 6.07 GΩ	---
 Prepared By		 Checked By		



TE-A 012017



Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)
 Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara,
 Pin Code : 391775. Gujarat, India.
 Telephone : 02667-264007, +91 88660 09021
 Email : erto@erto.in / sr.patel@erto.in
 Web : http://www.erto.in



ERTO

Quality Assurance Laboratory



Certificate no. TC-6229

Report No.: ERTO/TRP/1819/0820

ULR No.: TC62291900000186F

Date: 16/03/2019

Sr. No.	Particulars of test & cl.no.	Requirements as per specifications	Obtain value	Remarks
8.	Induced over-voltage withstand test : (As per cl.no.21.2(f) of IS 1180 (Part 1) : 2014) The test voltage of 866 Volts, 3 – phase was applied to the LV winding of the transformer and HV winding kept open. The supply frequency was maintained at 150 Hz. The test voltage was applied for 40 seconds.	Transformer shall withstand 866 volts at 150 Hz frequency for 40 seconds.	Withstood	Conforms
9.	Separate-source voltage withstand test : (As per cl.no.21.2(g) of IS 1180 (Part 1) : 2014) ➤ on HV winding: The test voltage of 70 kV ac, rms was applied between the shorted HV winding and earth. The tank and LV winding were shorted together and earthed. The test voltage was applied for 60 seconds. ➤ on LV winding: The test voltage of 3 kV ac, rms was applied between the shorted LV winding and earth. The tank and HV winding were shorted together and earthed. The test voltage was applied for 60 seconds.	Transformer shall withstand power frequency voltage of 70kv for 60 seconds. Transformer shall withstand power frequency voltage of 3kV for 60 seconds.	Withstood Withstood	Conforms
10.	Pressure test (routine test): (As per cl.no.21.2(h) of IS 1180(Part 1):2014) The transformer with bolted cover was tested at a pressure of 35 kPa above atmosphere pressure maintained inside the tank for 10 min.	There should be no leakage at any point	No leakage observed	Conforms
11.	Oil leakage test: (As per cl.no.21.2(j) of IS 1180 (Part 1) : 2014) The assembled transformer with all fittings including bushings in position was tested at a pressure equivalent to twice the normal head measured at the base of the tank for 8 hours.	There should be no leakage at any point	No leakage observed	Conforms

Prepared By

Checked By



TE-A 012018



Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)
 Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.
 Pin Code : 391775. Gujarat, India.
 Telephone : 02667-264007, +91 88660 09021
 Email : erto@erto.in / sr.patel@erto.in
 Web : http://www.erto.in



ERTO

Quality Assurance Laboratory



Certificate no. TC-6229

Report No.: ERTO/TRP/1819/0820

ULR No.: TC622919000000186F

Date: 16/03/2019

Sr. No.	Particulars of test & cl.no.	Requirements as per specifications	Obtain value	Remarks	
12.	Lightning impulse test with chopping: (As per cl.no.21.3(a) of IS 1180 (Part 1) : 2014 & test procedure followed as per cl. no. 14 of IS 2026 (Part 3): 2009)	Transformer shall withstand the test voltage	Withstood	Conforms	
			Peak Magnitude (kVP)		
			U-Phase (Tap-1)	V-Phase (Tap-5)	W-Phase (Tap-7)
1.	Reduced Impulse Wave	Upk -86.77	Upk -89.83	Upk -90.01	
2.	100 % full impulse wave	Upk -165.9	Upk -168.2	Upk -168.1	
3.	Reduced Chopped Impulse Wave	Upk -99.1	Upk -99.76	Upk -99.86	
4.	110 % full Chopped impulse wave	Upk -183.4	Upk -185.3	Upk -185.2	
5.	110 % full Chopped impulse wave	Upk -183.7	Upk -185.2	Upk -185.4	
6.	100 % full impulse wave	Upk -167	Upk -168.1	Upk -168.2	
7.	100 % full impulse wave	Upk -167.2	Upk -168.2	Upk -168.2	
<i>Basirani</i> Prepared By		<i>Basirani</i> Checked By			



TE-A 012019



Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)

Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.

Pin Code : 391775. Gujarat, India.

Telephone : 02667-264007, +91 88660 09021

Email : erto@erto.in / sr.patel@erto.in

Web : http://www.erto.in



ERTO

Quality Assurance Laboratory





Certificate no. TC-6229

Report No.: ERTO/TRP/1819/0820



ULR No.: TC622919000000186F

Date: 16/03/2019

U PHASE



1. Reduced Impulse Wave



2. 100% Full Impulse Wave

Prepared By
Prepared By

FORMAT NO.: FF-01, REV NO./DATE:01/11-02-2017



Checked By
Checked By

Page 12 of 26

TE-A 012020



Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)
 Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.
 Pin Code : 391775. Gujarat, India.
 Telephone : 02667-264007, +91 88660 09021
 Email : erto@erto.in / sr.patel@erto.in
 Web : http://www.erto.in



ERTO

Quality Assurance Laboratory





Certificate no. TC-6229



Report No.: ERTO/TRP/1819/0820

ULR No.: TC622919000000186F

Date: 16/03/2019



3. Reduced Chopped Impulse Wave



4. 110% Chopped Impulse Wave

Prepared By

Checked By





Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)

Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.

Pin Code : 391775. Gujarat, India.

Telephone : 02667-264007, +91 88660 09021

Email : erto@erto.in / sr.patel@erto.in

Web : http://www.erto.in



ERTO

Quality Assurance Laboratory





Certificate no. TC-6229



Report No.: ERTO/TRP/1819/0820

ULR No.: TC622919000000186F

Date: 16/03/2019



5. 110% Chopped Impulse Wave



6. 100% Full Impulse Wave

Aswary
Prepared By



[Signature]
Checked By



Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)
 Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.
 Pin Code : 391775. Gujarat, India.
 Telephone : 02667-264007, +91 88660 09021
 Email : erto@erto.in / sr.patel@erto.in
 Web : http://www.erto.in



ERTO

Quality Assurance Laboratory





Certificate no. TC-6229

Report No.: ERTO/TRP/1819/0820

ULR No.: TC622919000000186F

Date: 16/03/2019



7. 100% Full Impulse Wave

Prepared By
Prepared By



Checked By
Checked By

TE-A 012023



Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)
 Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.
 Pin Code : 391775. Gujarat, India.
 Telephone : 02667-264007, +91 88660 09021
 Email : erto@erto.in / sr.patel@erto.in
 Web : http://www.erto.in



ERTO

Quality Assurance Laboratory





Certificate no. TC-6229

Report No.: ERTO/TRP/1819/0820



ULR No.: TC622919000000186F

Date: 16/03/2019

V PHASE



1. Reduced Impulse Wave



2. 100% Full Impulse Wave

Prepared By *[Signature]*

Checked By *[Signature]*



TE - A 012024



Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)

Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.

Pin Code : 391775, Gujarat, India.

Telephone : 02667-264007, +91 88660 09021

Email : erto@erto.in / sr.patel@erto.in

Web : http://www.erto.in



ERTO

Quality Assurance Laboratory





Certificate no. TC-6229



Report No.: ERTO/TRP/1819/0820

ULR No.: TC622919000000186F

Date: 16/03/2019



3. Reduced Chopped Impulse Wave



4. 110% Chopped Impulse Wave

Prepared By
Prepared By



Checked By
Checked By



Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)

Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.

Pin Code : 391775. Gujarat, India.

Telephone : 02667-264007, +91 88660 09021

Email : erto@erto.in / sr.patel@erto.in

Web : http://www.erto.in



ERTO

Quality Assurance Laboratory





Certificate no. TC-6229



Report No.: ERTO/TRP/1819/0820

ULR No.: TC622919000000186F

Date: 16/03/2019



5. 110% Chopped Impulse Wave



6. 100% Full Impulse Wave

Prepared By
Prepared By



Checked By
Checked By



Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)

Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.

Pin Code : 391775, Gujarat, India.

Telephone : 02667-264007, +91 88660 09021

Email : erto@erto.in / sr.patel@erto.in

Web : http://www.erto.in



ERTO

Quality Assurance Laboratory





Certificate no. TC-6229

Report No.: ERTO/TRP/1819/0820

ULR No.: TC622919000000186F

Date: 16/03/2019



7. 100% Full Impulse Wave

Aparna
Prepared By

De
Checked By



TE-A 012027



Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)
 Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.
 Pin Code : 391775. Gujarat, India.
 Telephone : 02667-264007, +91 88660 09021
 Email : erto@erto.in / sr.patel@erto.in
 Web : http://www.erto.in



ERTO
Quality Assurance Laboratory





Certificate no. TC-6229

Report No.: ERTO/TRP/1819/0820



ULR No.: TC622919000000186F

Date: 16/03/2019

W PHASE



1. Reduced Impulse Wave



2. 100% Full Impulse Wave

Prepared By
Prepared By

Checked By
Checked By



TE-A 012028



Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)
 Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.
 Pin Code : 391775, Gujarat, India.
 Telephone : 02667-264007, +91 88660 09021
 Email : erto@erto.in / sr.patel@erto.in
 Web : http://www.erto.in



ERTO

Quality Assurance Laboratory





Certificate no. TC-6229



Report No.: ERTO/TRP/1819/0820

ULR No.: TC622919000000186F

Date: 16/03/2019



3. Reduced Chopped Impulse Wave



4. 110% Chopped Impulse Wave

Geera
Prepared By



De
Checked By

TE - A 012029



Electrical Research & Testing organisation™

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)

Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.

Pin Code : 391775, Gujarat, India.

Telephone : 02667-264007, +91 88660 09021

Email : erto@erto.in / sr.patel@erto.in

Web : http://www.erto.in



ERTO

Quality Assurance Laboratory





Certificate no. TC-6229



Report No.: ERTO/TRP/1819/0820

ULR No.: TC622919000000186F

Date: 16/03/2019



5. 110% Chopped Impulse Wave



6. 100% Full Impulse Wave

Sr Patel
Prepared By



SR
Checked By



Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)

Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.

Pin Code : 391775. Gujarat, India.

Telephone : 02667-264007, +91 88660 09021

Email : erto@erto.in / sr.patel@erto.in

Web : http://www.erto.in



ERTO

Quality Assurance Laboratory





Certificate no. TC-6229

Report No.: ERTO/TRP/1819/0820

ULR No.: TC622919000000186F

Date: 16/03/2019



7. 100% Full Impulse Wave

Oparya
Prepared By



Re
Checked By



Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)
 Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.
 Pin Code : 391775, Gujarat, India.
 Telephone : 02667-264007, +91 88660 09021
 Email : erto@erto.in / sr.patel@erto.in
 Web : http://www.erto.in



ERTO

Quality Assurance Laboratory



Certificate no. TC-6229

Report No.: ERTO/TRP/1819/0820

ULR No.: TC62291900000186F

Date: 16/03/2019

Sr. No.	Particulars of test & cl.no.	Requirements as per specifications	Obtain value	Remarks
13.	<p>Temperature-rise test : (Tap position : 7) (As per cl.no.21.3(b) of IS 1180 (Part 1) : 2014)</p> <p>Before starting test, the dimensions of tank with fins were measured & recorded.</p> <p>Size of tank : L- 1785 mm, W- 710 mm, H- 1835 mm (Avg.) No. of radiators: 04 No. of fins per radiator: 12 Size of fins: L-1600 mm, W-520 mm</p> <p>Losses fed for temperature-rise test were 18147.23 Watts (Measured no-load loss:2082.10 W and measured load loss at 75°C at tap no. 7: 16065.13 W) Measured losses were fed to the transformer (i.e. Supply was connected to HV winding and LV windings kept short-circuited) till steady state temperature-rise was attained. Top oil temperature was recorded hourly. After steady state condition, the losses were brought down in reference to the rated current one hour prior to shut down of HV and LV winding.</p>			Conforms
	A) Top oil temperature-rise :	Max. 40°C	36.3 °C	
	B) Winding Temperature Rise (Resistance method)			
	1) HV Winding:	Max. 45°C	38.3 °C	
	2) LV Winding:	Max. 45°C	40.2 °C	
	C) Ambient temperature at the time of reduced to rated current:		29.1 °C	
	D) Ambient temperature at the time of shut down:		28.1 °C	
	E) Time of shut down (Hrs):		22:00	

Prepared By

Checked By





Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)

Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.

Pin Code : 391775. Gujarat, India.

Telephone : 02667-264007, +91 88660 09021

Email : erto@erto.in / sr.patel@erto.in

Web : http://www.erto.in



ERTO

Quality Assurance Laboratory





Certificate no. TC-6229

Report No.: ERTO/TRP/1819/0820

ULR No.: TC62291900000186F

Date: 16/03/2019

Sr. No.	Particulars of test & cl.no.	Requirements as per specifications	Obtain value	Remarks	
14.	Pressure test (type test): (As per cl.no.21.3(d) of IS 1180(Part 1):2014)			Conforms	
	The transformer tank was subjected to air pressure of 80 kPa for 30 minutes. The permanent deflections of flat plates were recorded, after pressure has been released.				
	Deflection measured at	Length of plate (mm)			
	HV side	1785	Max. 9.0 mm		2.0 mm
	LV side	1785	Max. 9.0 mm		2.0 mm
	Side A	710	Max. 5.0 mm		1.0 mm
	Side B	710	Max. 5.0 mm		1.0 mm
	The transformer tank was subjected to vacuum of 500 mm of Mercury for 30 minutes. The permanent deflections of flat plates were recorded, after vacuum has been released.				
	Deflection measured at	Length of plate (mm)			
	HV side	1785	Max. 9.0 mm		1.0 mm
	LV side	1785	Max. 9.0 mm		1.0 mm
	Side A	710	Max. 5.0 mm		0.0 mm
	Side B	710	Max. 5.0 mm		0.0 mm
	<div style="border: 1px solid black; padding: 10px; text-align: center;"> HV SIDE SIDE A SIDE B LV SIDE </div>		There should be no air leakage at any point		No air leakage observed
 Prepared By		 Checked By			



TE-A 012033



Electrical Research & Testing organisationTM

(Accredited by the National Accreditation Board for Testing and Calibration Laboratories, Govt. Of India)
 Plot No. 747, Manjusar Village, B/H Gurukrupa Farm, Savli-Vadodara Road, Ta.: Savli, Dist.: Vadodara.
 Pin Code : 391775, Gujarat, India.
 Telephone : 02667-264007, +91 88660 09021
 Email : erto@erto.in / sr.patel@erto.in
 Web : http://www.erto.in



ERTO

Quality Assurance Laboratory



Certificate no. TC-6229

Report No.: ERTO/TRP/1819/0820

ULR No.: TC622919000000186F

Date: 16/03/2019

Sr. No.	Particulars of test & cl.no.	Requirements as per specifications	Obtain value	Remarks																																												
15.	<p>Determination of sound levels: (As per cl. no. 21.4(a) of IS 1180 (Part 1):2014) Load condition : As per cl. no. 6.2 of IS 2026 (Part 10):2009 No-load current and rated voltage Calculation of the area of the measurement surface : As per cl. no. 10.1 of IS 2026 (Part 10):2009 Measurement made at 0.3 m from the principal radiating surface Sound pressure method As per cl. no. 11.3 of IS 2026 (Part 10):2009</p> <table border="1"> <thead> <tr> <th>Location of measurement</th> <th>Ambient noise Before object energized (dB)</th> <th>Ambient Noise when object energized (dB)</th> <th>Ambient noise after object de-energized (dB)</th> </tr> </thead> <tbody> <tr><td>1</td><td>34.9</td><td>43.4</td><td>33.9</td></tr> <tr><td>2</td><td>34.2</td><td>43.7</td><td>34.2</td></tr> <tr><td>3</td><td>34.0</td><td>43.1</td><td>33.8</td></tr> <tr><td>4</td><td>33.8</td><td>42.9</td><td>33.6</td></tr> <tr><td>5</td><td>33.6</td><td>42.8</td><td>34.1</td></tr> <tr><td>6</td><td>33.7</td><td>43.2</td><td>33.8</td></tr> <tr><td>7</td><td>33.9</td><td>43.0</td><td>33.9</td></tr> <tr><td>8</td><td>33.8</td><td>42.9</td><td>34.0</td></tr> <tr><td>9</td><td>34.4</td><td>43.4</td><td>33.7</td></tr> <tr><td>10</td><td>34.1</td><td>43.2</td><td>34.3</td></tr> </tbody> </table> <p>The uncorrected average A-weighted sound pressure level $\overline{L_{pA0}}$: 43.2 dB</p> <p>The average A-weighted background noise pressure level before the test object energized $\overline{L_{bgA}}$: 34.1 dB</p> <p>The average A-weighted background noise pressure level after the test object de-energized $\overline{L_{bgA}}$: 33.9 dB</p> <p>The corrected average A-weighted sound pressure level $\overline{L_{pA}}$: 37.5 dB</p> <p>The calculated A-weighted sound power level L_{WA} : 52.9 dB</p> <p>Max. 62 dB (As specified by customer)</p>	Location of measurement	Ambient noise Before object energized (dB)	Ambient Noise when object energized (dB)	Ambient noise after object de-energized (dB)	1	34.9	43.4	33.9	2	34.2	43.7	34.2	3	34.0	43.1	33.8	4	33.8	42.9	33.6	5	33.6	42.8	34.1	6	33.7	43.2	33.8	7	33.9	43.0	33.9	8	33.8	42.9	34.0	9	34.4	43.4	33.7	10	34.1	43.2	34.3			---
Location of measurement	Ambient noise Before object energized (dB)	Ambient Noise when object energized (dB)	Ambient noise after object de-energized (dB)																																													
1	34.9	43.4	33.9																																													
2	34.2	43.7	34.2																																													
3	34.0	43.1	33.8																																													
4	33.8	42.9	33.6																																													
5	33.6	42.8	34.1																																													
6	33.7	43.2	33.8																																													
7	33.9	43.0	33.9																																													
8	33.8	42.9	34.0																																													
9	34.4	43.4	33.7																																													
10	34.1	43.2	34.3																																													
<p>Prepared By <i>[Signature]</i></p>		<p>Checked By <i>[Signature]</i></p>																																														



DISTRIBUTION TRANSFORMER
RECONS POWER EQUIPMENTS PVT. LTD.
 FARIDABAD - 121004
 PH : (0129) 4082114 - 6

3 PHASE TRANSFORMER


STANDARD	IS 1180 (PART 1)	ENERGY EFFICIENCY LEVEL	3
KVA	2500	MAX. TOTAL LOSSES AT 50% RATED LOAD	W 6342.5
VOLTS AT NO LOAD	HV 33000	MAX. TOTAL LOSSES AT 100% RATED LOAD	W 18812.5
	LV 433	TYPE OF COOLING	ON AN
BIL	HV 170/70	TEMP RISE	OIL °C 40
	LV		WDG °C 45
AMPERES	HV 43.73	MASS OF OIL	KG 1730
	LV 3333.43	TOTAL MASS	KG 8750
FREQUENCY	Hz 50	VOLUME OF OIL	LTR 2050
VECTOR GROUP	Dyn 11	MONTH & YEAR OF MFG	MARCH 2019
IMPEDANCE VOLT %	8.25	SERIAL NO.	5432/02/19
TAPPINGS	OFF CKT		

FOR HV VARIATION IN STEPS FROM % TO %

CUSTOMER _____
 ORDER NUMBER _____

MADE IN INDIA


SWITCH POSITION	CONNECTIONS	NO LOAD VOLTAGE	
		HV	LV
1	5-6	36300	433
2	6-4	35475	433
3	4-7	34650	433
4	7-3	33825	433
5	3-8	33000	433
6	8-2	32175	433
7	2-9	31350	433



ERTO
 Test Report No : GR/173011910820
 Date : 16/12/19
 Sample : 2500 KVA
 Verified by : [Signature]
 Verification of this drawing by ERTO is limited to relevant dimensional checks only.
 Verified dimensions are marked with *




SCALE N T S	DRN BY MR. BNJ-	PC NO. & DATE	
	CHD BY M. YADAV	DRG. NO	RC/18-10/2500/01
	PASS BY	REVISION & DATE	00
CLIENT			
Recons Power Equipments Pvt. Ltd. (formerly known as RECTIFIERS & CONTROLS) PLOT NO. 38, SECTOR-25, FARIDABAD-121004 (HARYANA) Ph. : 0129-4062114-16, Fax : 0129-4065111, 4151323 Email : admin@reconsindia.com Website : www.reconsindia.com			



APPROX. WEIGHT IN KGS.

CORE & WINDING IN KGS.	4550
OIL IN KGS.	1730
OIL IN LITRS	2050
TOTAL WEIGHT KGS.	8750



- NOTES:-**
- 1) ALL DIMENSIONS ARE IN mm
 - 2) ALL DIMENSIONS & WEIGHT ARE SUBJECT TO +10% TOLERANCE.
 - 3) TAPPINGS ON HV FOR HV VARIATION OF +10% TO -5% IN STEP OF 2.5% BY OFF CRT.
 - 4) PAINT - POLYURETHANE SHADE NO 631 OF I.S. : 5
 - 5) POSITION OF FITTINGS SHOWN ARE INDICATIVE. ITS POSITION & SHAPE OF FITTINGS MAY CHANGE WHILE ACTUAL DESIGN & MANUFACTURING.
 - 6) MIN CLEARANCES :-

33 KV	0.433 KV
350	25
320	20

PHASE TO PHASE
PHASE TO EARTH

TANK INSIDE DIMENSIONS IN mm

LENGTH	1785
WIDTH	710
HEIGHT	1835 (Avg.)
HEIGHT	1830 (HV SIDE)
HEIGHT	1840 (LV SIDE)

SR.NO	DESCRIPTION	QTY
30	TRANSPORT OIL LEVEL GAUGE	1
29	POCKET FOR W.T.I.	1
28	POCKET FOR O.T.I.	1
27	DOUBLE FLOAT BUSHHOLEZ RELAY WITH ALARM & TRIP CONTACTS (GOR 2)	1
26	BOTTOM DRAIN CUM SAMPLING VALVE (20 mmØ S. S. F.)	1
25	RADIATOR VALVES (BUTTERFLY TYPE)	8
24	SHUT-OFF VALVE (50 mmØ O.S.F.) C-M. GATE VALVE	2
23	TOP FILTER VALVE (32 mmØ. S. F.)	1
22	BOTTOM FILTER VALVE (32 mmØ D. S. F.)	1
21	JACKING PADS	4
20	INSPECTION COVER	1
19	EXPLOSION VENT WITH OIL SIGHT GLASS AND DOUBLE DIAPHRAGM	1
18	SILICA GEL BREATHER (1 kgs) WITH FLANGE	1
17	LIFTING LUGS FOR COMPLETE TRANSFORMER	4
16	PNEUMATIC TYPE OIL LEVEL GAUGE	1
15	CONSERVATOR WITH LIFTING LUGS, OIL FILLING CAP & DRAIN PLUG	1
14	LIFTING LUGS FOR TOP COVER	4
13	P.S. RADIATORS WITH AIR RELEASE PLUG, LIFTING LUG & DRAIN PLUG RADIATORS SIZE - 520 x 1600 x 12 FINS	4
12	THERMOMETER POCKET	2
11	AIR RELEASE PLUG	1
10	NATING AND DIAGRAM PLATE	1
9	EARTHING TERMINALS (M-18)	2
8	BASE CHANNEL WITH HULLING HOLE	2
7	200 Ø FLAT ROLLERS (BI-DIRECTIONAL)	4
6	WARNING PLATE FOR TAP SWITCH	1
5	TAPPING SWITCH HANDLE WITH POSITION INDICATOR & LOCKING DEVICE	1
4	ADDITIONAL NEUTRAL BRONZ BUSHING (1 KV/2152 Amps)	1
3	L.V. CABLE BOX WITH DCC (1KV/4000 Amps)	1
2	H.V. BARE PORCELAIN BUSHING (36 KV/250 Amps)	3
1	TRANSFORMER TANK	1

DRN	
CHD	
APPROD	
GENERAL ARRANGEMENT	
OF TRANSFORMER	
2500 KVA, 33/0.433 KV	
DATE	
NO	
BY	
RECORD	
SCALE	N.T.S.
SHEET	1/1
NO	
ORG. NO.	RC/18-19/2909/02



ERTO

Test Report No.: ERTO/19/07/19/108/10
 Date: 16/3/19
 Sample: 2500 KVA
 Verified by: [Signature]
 Verification of this drawing by ERTO is limited to relevant dimensions checks only.
 Verified dimensions are marked with *

